

**MODIFICATIONS / ADDITIONS / ALTERATIONS IN EXISTING CTI
BUILDING LOCATED AT BAREILLY (UP) ON BEHALF OF
PRIVATE BROADCASTERS FOR FM PHASE - III (BATCH – 1)**

**TENDER FOR PRIVATE FM BROADCASTERS FLOATED BY:
BROADCAST ENGINEERING CONSULTANTS INDIA LIMITED
14 – B, RING ROAD, INDRAPRASTHA ESTATE, NEW DELHI – 110002**

Submitted by (Tenderer)

For BECIL

CONTENTS

S.NO	TITLE
1	TENDER NOTICE
2	DECLARATION
3	PREFACE & SCOPE OF WORK
4	GENERAL CONDITION OF CONTRACT
5	CLAUSES OF CONTRACT
6	SPECIFICATIONS
7	SCHEDULE F
8	APPENDIX “1”
9	BILL OF QUANTITIES (CIVIL & ELECTRICAL)

NOTICE INVITING TENDER

BROADCAST ENGINEERING CONSULTANTS INDIA LIMITED, invites sealed item rate tenders on behalf of Private FM Broadcasters from Contractors for the following work :-

Name of work: Modifications / Additions / Alterations in existing CTI building located at BAREILLY (UP) on behalf of Private Broadcasters for FM Phase - III (Batch – 1).

Time period: 3 (Three) Months after award of work

Estimated Cost put to bid: - **Rs. 16,18,000/-**

Earnest Money Deposit: Rs. **32,500/-** in the form of DD / Pay order / Bankers Cheque in favour of BECIL payable at Delhi/New Delhi

Sale of Tender Documents: w.e.f. 21/04/2016 to 26/04/2016

Last date for submission of Tender: 29/04/2016 up to 2 pm (1400Hrs)

Date of opening of Tender: 29/04/2016 at 02:30 pm (1430Hrs)

Tender documents may be obtained from the corporate office, BECIL BHAWAN, C- 56 / A17, Sector 62, Noida-201307 (U.P) on all working days between 1100 hrs to 1600hrs. on payment of Rs. 500/- (in cash / Pay order / DD in favour of BECIL payable at Delhi / New Delhi.

The tender documents can also be downloaded from BECIL website : www.becil.com. However the agencies have to submit Rs. 500/- in the form of pay order / DD in favour of BECIL Payable at Delhi/ New Delhi towards the cost of tender document.

NOTE: The Tenderer

1. Must have done at least one similar Work of not less than Rs 25 lakhs in one year or two works of not less than Rs 20 lakhs in two years during the period of last 3 years
2. Must have the following Registration / Certificates or any other Certificate required by the Government from Building Contractors.
 - a) PAN no.
 - b) Sales Tax Registration/TIN No.
 - c) Service Tax Registration
3. May visit the site before submission of tender to understand clearly the nature and scope of work involved.
4. Must submit cost of tender document, EMD, work experience and above mentioned certificates in separate envelops at the time of submission of tender document.
5. Tenders of the agencies who do not submit cost of tender document, EMD and the above mentioned certificates shall be rejected.

Tender should be forwarded to:

The Chairman & Managing Director
BROADCAST ENGINEERING CONSULTANTS INDIA LIMITED (BECIL)
C-56 / A-17, SECTOR 62, NOIDA -201307 (U.P)

DECLARATION

Tender for the work of modifications / additions / alterations in existing CTI building located at BAREILLY (UP) on behalf of private broadcasters for FM PHASE - III (BATCH – 1)

- (i) To be submitted by 14:00 hours on 29/04/2016
- (ii) To be opened in presence of tenderer who may be present at 14:30 hr on 29/04/2016 in the office of CMD, BECIL Noida.
- (iii) Issued to M/s:

Signature of the contractor.....

Designation of issuing authority

TENDER

I/We have read and examined the notice inviting tender, Schedule F, appendix 1, applicable Specifications, BOQ, General conditions of contract, clauses of Contract & other documents and rules referred to in the Clauses of contract and all other contents in the tender document for the work Modifications/Addition/Alteration in CTI Buildings for Private FM Phase III (Batch 1) at BAREILLY (UP).

I/We hereby tender for the execution of the work specified within the time specified in, schedule of quantities and in accordance in all respects with specification, designs, drawings and instructions in writing referred to in the Conditions of Contract and with such materials as are provided for, by, and in respects in accordance with, such conditions so far as applicable. We agree to keep the tender open for sixty (60) days from the due date of its opening and not to make any modifications in its terms and conditions.

A sum of Rs 32,500/- has been deposited by DD/Pay order / Banker's cheque payable to BECIL issued by a schedule bank as Earnest Money. If I/we fail to furnish the prescribed performance guarantee within prescribed period, I/we agree that the said CMD BECIL or his successors in office shall without prejudice to any other right or remedy, be at liberty to forfeit the said earnest money absolutely. Further, if I/we fail to commence work as specified, I/we agree that CMD BECIL or his successors in office shall without prejudice to any other right or remedy available in law, be at liberty to forfeit the said earnest money and the performance guarantee absolutely. Otherwise, the said earnest money shall be retained by him towards security deposit to execute all the works referred to in the tender documents upon the terms and conditions contained or referred to there in and to carry out such deviation as may be ordered, up to a maximum of the percentage mentioned in **SCHEDULE 'F'** and those in excess of that limit at the rates to be determined in accordance with the provision contained in tender form.

Submitted by (Tenderer)

For BECIL.

Further, I/We agree that in case of forfeiture of earnest money or both Earnest Money & Performance Guarantee as aforesaid, I/We shall be debarred for participation in the re-tendering process of the work.

I/We hereby declare that I/we shall treat the tender documents drawings and other records connected with the work as secret/confidential documents and shall not communicate information derived there from to any person other than a person to whom I/we am/are authorized to communicate the same or use the information in any manner prejudicial to the State.

Dated

Signature of Contractor

Witness:

Postal Address

Address:

Occupation:

A C C E P T A N C E

The above tender is accepted by me for and on behalf of the BECIL for a sum of
Rs.....(Rupees.....
.....)

The letters referred to below shall form part of this Contract Agreement:-

- (a)

- (b)

- (c)

For & on behalf of the BECIL

Signature.....

Designation.....

Dated.....

PREFACE AND SCOPE OF WORK

1.0 PREFACE

M/S BROADCAST ENGINEERING CONSULTANTS INDIA LIMITED (BECIL) propose to get executed the work of modifications / additions / alterations in existing CTI building located at BAREILLY (UP) on behalf of private broadcasters for FM phase - III (Batch – 1).

1.1 M/s Environment Design Consultants (EDC), A-194, Gujranwala Town, Part-1, Delhi-110033 are the Project Architect Consultants to BECIL for this Project. They are in-charge of preparing plans, drawings, specifications etc. advising and assisting BECIL to interpret the tender documents and to carry out inspection of works including structural design and acceptance of such work, checking of bills presented by the Contractor and recommend payment and final settlement of bills.

1.2 **TYPE OF WORK/BRIEF:** - The building under consideration is an extension of single storey structure horizontally in prefabricated insulated puff panels with 100mm puff insulated sandwich external walls, 50mm puff insulated sandwich panels in the roof. Roof is supported on MS purlins. However some walls may have to be in brick work over plinth. The platform below plinth level shall also be in brick work.

The new extension to the building shall be of approximate 3.5 meters height. The work shall also include electrical, Water supply and Sanitary works apart from addition and alteration works. Any external development like boundary walls, roads, sewage, storm water lines, septic tanks, rain water harvesting pits, overhead water tanks, earthing pits, soak pits, are included in the scope.

The works will also include repair work of the existing building and repair work consequent to the extension of the building as identified in Section-B of the BOQ.

1.3 LIST OF ITEMS TO BE EXECUTED

- a) Cement Concrete work
- b) Brick Work
- c) Reinforced cement concrete work
- d) Painting
- e) Puff panel in roofing
- f) Puff panel in external walls
- g) Internal/ External electrical work
- h) Sanitary and water supply works etc.
- i) False Ceiling
- j) MS Structure
- k) Earth Work-(1) Excavation. (2) Back Filling. (3) Earth filling with earth brought

from outside.

- l) Cement Plaster
- m) Fire Fighting Equipments
- n) Aluminum work and glazing

Structural design and drawings shall be issued by Architect consultants and periodic supervision shall be by BECIL Representative.

Note: Any discrepancy/dispute regarding scope of work will be decided by the Architect Consultants i.e. M/s EDC in consultation with BECIL that shall be binding on the Contractor.

1.4 The joint measurements of works shall be done by the Contractor along with BECIL Representative & will be recorded in MB's by the Contractor, who will send one copy each to BECIL representative on site, & Architect consultants i.e. M/s EDC. The Architect consultants after receiving checked bill from BECIL representative, within 10 days, shall issue the certificate of recommended payments. In all, BECIL will take 30 days to clear the bill, after deducting security deposit @ 5% from amount of each running bills. This will be released post successful completion and rectification of defects after expiry of the defects liability period of twelve months.

1.5 Two sets of drawings will be issued by the Architect consultants free of cost but subsequent copies will be issued @ Rs.300/- per drawing to the Contractor.

1.6 The Contractor at his own cost shall provide necessary pumps/generator; arrange electricity and water supply, hoist and T&P etc for carrying out the works. Cost of any new storage built for the works, will be borne by the Contractor.

1.7 The following items may have to be executed but no extra payment will be made.

- (a) Temporary chowkidar hut, labour huts, site office, etc if constructed on site shall be cleared from the site on completion of the works by the contractor at his own cost.
- (b) The layout of building shall be marked on site by the contractor for approval of BECIL Representative / Architect Consultants.
- (c) Miscellaneous Site preparation for taking up the work.

2. GENERAL CONDITIONS OF CONTRACT

2.1 The Contractor's rates shall include the cost of labour, transportation of labour, materials, T&P etc at the site and his own profit, over heads and taxes including ESI, PF, Works Contract Tax, Octroi, Service tax etc.

2.2 The Principals BECIL reserves the right of accepting the whole or any part of the tender and the tenderer shall be bound to perform the same at the quoted rates.

- 2.3** For interpreting the specifications or in case of any ambiguity the following order of decreasing importance shall be followed:
- a) The price Bill of Quantities.
 - b) The additional / Technical Specifications.
 - c) Drawings
 - d) Conditions of Contract.
 - e) Instructions from the Project Architect / BECIL Representative in writing.
 - f) CPWD specifications, with up to date correction slips.
- 2.4** **EMD:** An earnest money deposit (EMD) of Rs 32,500/- will be submitted by the Tenderer by a DD /Pay order / Banker's cheque in favour of BECIL. The EMD of the successful tenderer shall be adjusted towards security deposit, whereas the EMD of the unsuccessful tenderers shall be returned within 15 days of the finalization of the tender. The EMD shall not carry any interest. After acceptance of the tender the tenderer shall sign the necessary contract papers within 7 days of the issue of acceptance letter. In case of delay the Earnest Money will be forfeited or tender cancelled.
- 2.5** The Contractor shall not be entitled to any compensation for any loss suffered by him on account of any delay in commencing or executing the work, whatsoever be the cause for such delays including delays in procuring Government Controlled or other materials.
- 2.6** Different items to be executed are for all heights, depths, curvatures and widths unless otherwise specified.
- 2.7** The detailed schedule of program in the form of PERT-chart/ bar chart/activity chart for the whole work shall be drawn in consultation with the Architects/ BECIL representative, and submitted within 7 days of the Award of Work by the contractor. The work shall be progressed and monitored from week to week and completed in the stipulated time of contract and according to the approved Schedule.
- 2.8** If BECIL wants to occupy areas in part, the Contractor shall have to complete the work of these areas in consultation with Architect consultants and hand over the same to BECIL without affecting any of the clauses of contract agreement.
- 2.9** The principals BECIL does not bind itself to accept the lowest or any other tender, and reserve to itself the authority to reject any or all tenders received without assignment of any reason. All Tenders in which any of the prescribed condition is not fulfilled or is incomplete in any respect are liable to be rejected.
- 2.10** No extension of time will be allowed to the Contractor due to weather conditions prevalent in the area. The Contractor is expected to take all the precautions at his own cost so that the work, workmanship and the materials are not affected in the inclement weather.
- 2.11** The work as described in the Contract, drawings & specification shall be completed within 3 months from the date of award of work.

- 2.12 Extra items:** Rates of all extra items or additional, altered or substituted items shall be worked out as per CPWD norms and will include 15% for contractors profit including overheads. The rates for extra/substituted items shall be got approved from the BECIL Representative upon advice of the Architect Consultants before execution of the work. Any error in sanction of the rates is liable to be revised at any time by BECIL.
- 2.13** BECIL reserves the right of constructing any part of the building or any additional work being part of the project themselves and contractor shall have no claims on the work carried out.
- 2.14** The contractor shall take care and precautions for safeguarding of the existing building installations during execution of work. He shall be accountable during the construction of the building. The Contractor should ensure all new openings during construction are secured & water tight. He should also ensure existing FM Pvt & Govt. broadcasters working is not effected in any situation during execution of work.
- 2.15** Receipts shall be provided by the contractor of any payments received for the works done as per CPWD accounting practices. No payment will be made unless contract is signed by the contractor.
- 2.16** The Main Contractor shall assist / co-operate with all other sub contractors even if employed by BECIL themselves directly during the period of contract or during extended period.
- 2.17** BECIL reserves the right to get any of the any specialized work items executed directly by Sub Contractors if deemed fit by them.
- 2.18** Electrical and water connection at site is to be arranged by the contractor at his own cost. The Contractor shall make arrangement for electrification or electricity for pumping and lighting required all around the site.
- 2.19** Ground Floor- The ground floor shall be the slab or floor immediately above the prevailing site levels determined by the Project Architect.
- 2.20** The Contractor shall keep the site clean of debris and other unwanted materials during construction and handover the site complete and clear of all building rubbish or any unwanted material, labour huts or equipment of the Contractor etc.
- 2.21** Use of correctional fluid anywhere in the tender document is not permitted and such tender is liable to be rejected.
- 2.22 Employment of Technical staff and employees:**
The contractor shall provide all necessary superintendence during execution of the work and as long thereafter as may be necessary for proper fulfilling of the obligations under the contract.

The contractor shall immediately after receiving letter of Award of the contract and before commencement of the work, intimate in writing to the BECIL Representative details like name, address, qualification etc of the principal technical representative to be in charge of the work. Such qualification shall not be lower than specified in Schedule 'F'. BECIL

Representative shall within 7 days of receipt of such communication intimate in writing his approval or otherwise of such representative to the contractor.

3.0 PERFORMANCE GUARANTEE

- (i) The successful tenderer shall submit an irrevocable Performance Guarantee of 5% (Five percent) of the tendered amount in addition to other deposits mentioned elsewhere in the contract for his proper performance of the contract agreement, (not withstanding and/or without prejudice to any other provisions in the contract) within period specified in Schedule 'F' from the date of issue of letter of acceptance. This period can be further extended by BECIL Representative upto a maximum period as specified in schedule 'F' on written request of the contractor stating the reason for delays in procuring the Performance Guarantee, to the satisfaction of the Architect Consultants /BECIL Representative. This guarantee shall be in the form of Cash (in case guarantee amount is less than Rs. 10,000/) or Deposit at Call receipt of any scheduled bank/Banker's Cheque of any scheduled bank/Demand Draft of any scheduled bank/Pay Order of any scheduled bank (In case guarantee amount is less than Rs. 1,00,000/) or Government Securities or Fixed Deposit Receipts or Guarantee Bonds of any Scheduled Bank or the State Bank of India in accordance with the form annexed hereto. In case a fixed deposit receipt of any Bank is furnished by the contractor to the Government as part of the performance guarantee and the Bank is unable to make payment against the said fixed deposit receipt, the loss caused thereby shall fall on the Contractor and the contractor shall forthwith on demand furnish additional security to BECIL to make good the deficit.
- (ii) The Performance Guarantee shall be initially valid upto the stipulated date of completion plus 60 days beyond that in case the time for completion of work gets enlarged; the contractor shall get the validity of Performance Guarantee extended to cover such enlarged time for completion of work. After recording of the completion certificate for the work by the competent authority, the performance guarantee shall be returned to the contractor, without any interest.
- (iii) The Architect consultants/BECIL Representative shall not make a claim under the performance guarantee except for amounts to which BECIL is entitled under the contract (not withstanding and/or without prejudice to any other provisions in the contract agreement) in the event of.
 - (a) Failure by the contractor to extend the validity of the Performance Guarantee as described herein above, in which event BECIL may claim the full amount of the Performance Guarantee.
 - (b) Failure by the contractor to pay BECIL any amount due, either as agreed by the contractor or determined under any of the Clauses/Conditions of the agreement, within 30 days of the service of notice to this effect by Architect consultants/BECIL Representative.
- iv) In the event of the contract being determined or rescinded under provision of any of the Clause/Condition of the agreement, the performance guarantee shall stand forfeited in full and shall be absolutely at the disposal of the BECIL

4.0 SECURITY DEPOSIT

- 4.1 The Contractor whose Tender is accepted will be required to furnish by way of Security Deposit for the fulfillment of his Contract a sum of money to be @ 5% of the tendered costs to be adjusted from the running bills, the maximum total sum shall be Rs. 5.0 Lacs.
- 4.2 Security deposit, Performance Guarantee and Earnest Money will not carry any interest during the period.
- 4.3 Security deposit shall be refunded on expiry of Defects Liability Period of one year on successful completion and rectification of defects to the satisfaction of BECIL/Architect Consultants
- 4.4 Any defect developed within Defect Liability Period from the date of completion will have to be rectified by the Contractor at his own cost.
- 4.5 The said Security deposit shall indemnify BECIL against loss from defects arising under any clause of this contract or due to the failure of the Contractor to carry out promptly any repairs, correction or instructions under the contract

5.0 PROVISIONS FOR LABOUR

- 5.1 Payments to labour shall be as per law & shall be paid to the satisfaction of BECIL. Photocopy of the receipts is to be submitted by the contractor on demand. No labour complaint shall be entertained by BECIL. However in the event of non payment to the labour by the contractor BECIL reserves the right to deduct the payment involved from the running bills of the contractor & pay to the complainant labour.
- 5.2 The contractor shall comply with all the provisions of the Minimum Wages Act, 1948, and Contract Labour (Regulation) Act, 1970, amended from time to time and rules framed there under and other labour laws effecting.
- 5.3 Medical facilities (as per law) for workers will be provided by the Contractors at their cost including insurance for the workers engaged for the execution of works
- 5.4 **Protections of health and sanitary arrangement for workers**
Model Rules for the protection of health and sanitary arrangements for workers \ employed by C.P.W.D. or its contractors shall be applicable.
- 5.5 **Safety code**
All precautions and safety measures shall be adopted as per CPWD safety code applicable for all GOVT works.

6.0 SECURITY OF MATERIALS

Safe custody of Material, supplied to the Contractors or material purchased by him for the works is the responsibility of the Contractor, including its watch and ward.

SPECIAL CLAUSES OF CONTRACT

7.0 DEFINITIONS

BROADCAST ENGINEERING CONSULTANTS INDIA LIMITED.
14 – B, RING ROAD, INDRAPRASTHA ESTATE, NEW DELHI – 110002

The Principles

THE CONTRACTOR-

THE ARCHITECTS -

M/s Environment Design Consultants
A-194, Gujranwala Town, Part-1, Delhi-110033

- 7.1 Any of those mentioned above as such in the agreement shall include their legal representative's assignees or successors and are treated through out the contract document as if each were of singular number and masculine gender.
- 7.2 "The **Site**" shall mean the site of the contract work, i.e. at CTI building BAREILLY (UP) including any building, and erection there on, and any other land allotted by the Principles for Contractor to use.
- 7.3 The work shall not be sub let by the contractor without permission of BECIL. The term "**Sub-Contractor**" "as employed herein, includes those having a direct contract with the Contractor includes one who furnishes material worked to a special design according to the plans or specification of the work but does not include one who merely furnished material not so worked. Anyone doing work on a piece rate basis shall be deemed a sub-Contractor.
- 7.4 The work to be executed is modification of existing building with functional services. The working hours for the civil modification works will have to be coordinated to ensure minimal inconvenience to the existing users.
- 7.5 Written notice shall be deemed to have been duly served if delivered in person to the individual or to a member of the firm or if delivered at or sent by registered mail to the last business address available to BECIL.
- 7.6 The term "work" of the Contractor includes execution of the work.
- 7.7 All time limits stated in the Contract Document are the essence of the Contract.
- 7.8 The law of the place of the work shall govern the construction under this Contract.

8.0 ARTICLE OF AGREEMENT

The following documents shall constitute the contract documents.

- a) Preface & Scope of work
- b) General Condition of Contract
- c) Clauses of Contract
- d) Bill of Quantities
- e) C.P.W.D. specifications with up to date correction slips.
- f) Drawings issued by Architect/ BECIL from time to time.
- g) Schedule – F & Appendix-1.

- 8.1** The several documents forming the contract are to be taken as mutually explanatory of one another, detailed drawings being followed in preference to small scale drawing and figured dimensions in preference to scale and special conditions in preference to General Conditions. If there are varying or conflicting provisions made in any one document forming part of the contract, BECIL shall be the deciding authority with regard to the intention of the document and BECIL's decision shall be final and binding on the contractor.
- 8.2** The Contractor shall keep one copy of the CPWD specifications, with descriptive schedule or other like document referred to in this document and one copy of the Contract Drawings and such other drawings, supplied to him from time to time so as to be available to the principles or the Architect or his representative at all reasonable times.
- 8.3** Upon final payment under the clauses of the contract, the Contractor shall if requested by the Architect Consultants forthwith return to the Architect all drawings, details, specifications and other document of like nature which bears his name or that of the Architect consultants.
- 8.4** Any other clauses or conditions not covered by this Agreement shall be governed by the CPWD manuals & form part of the Agreement. Mode of measurement shall be as per CPWD norms.

9.0 TYPE OF CONTRACT

The Contract shall be an Item Rate Contract.

10.0 CONTRACT DRAWINGS

- 10.1** Project Architect shall issue the basic drawings as & when required. Claim for delay in getting these drawings will not be accepted. Completion of work is considered a joint responsibility. A request for preparing required/additional drawings shall be sent to the Project Architect for any basic drawing 7 days in advance.
- 10.2** In general the drawings supplied by BECIL Representative/Architect Consultants shall indicate the dimension, position and type of construction. Any additional drawings like working details, structural details etc shall be issued by the Architects after approval from BECIL.
- 10.3** The Contractor's work shall not deviate from the drawings and specifications. The Architect Consultants interpretation of these document shall be final and without appeal.
- 10.4** Error, inconsistencies discovered in the drawings and specifications shall be promptly brought to the attention of the Architect Consultants, through the BECIL site incharge on

site for interpretation or correction. Local conditions, which may affect the work, shall likewise be brought to the notice of Architects consultants. If at any time, it is discovered that work is being done which is not in accordance with the Contract drawings and specifications, the Contractor shall correct the work immediately. Rectification of defective work shall not be the basis for any claim for extension of time of completion. The Contractor shall not carry on such work except with the knowledge of the Project Architect Consultants or BECIL representative.

10.5 Figured dimensions on the scale drawing and large size details shall govern construction. These drawings shall take precedence over small-scale drawings. Any work done before receipt of such details and not in accordance with the same, shall as directed, be removed and replaced or adjusted by the Contractor without expense to BECIL. The general conditions apply with equal force to all the works including authorized extra work and work executed by the sub-contractor.

10.6 All the drawings and specifications and copies thereof, furnished by the Architects are his property. They shall not be used on any other work and shall be returned to the Architect Consultants / BECIL on Completion of the Contract.

11.0 CONTRACT SUM

11.1 If a discrepancy is found, the rates which correspond with the amount worked out by the contractor shall unless otherwise proved be taken as correct. If the amount of an item is not worked out by the contractor or it does not correspond with rates written either in figures or in words, then the rates quoted by the contractor in words shall be taken as correct. Where the rates quoted by the contractor in figures and in words tally but the amount is not worked out correctly, the rates quoted by the contractor will unless otherwise proved be taken as correct and not the amount. In event no rate has been quoted for any item(s), leaving space both in figures (s), words (s) and amount blank, it will be presumed that the contractor has included the cost of this/these item (s) in other items and rate for such items(s) will be considered as zero and work will be required to be executed accordingly.

11.2 Any error in description or omission of items from the contract bills shall not vitiate this contract but shall be corrected and deemed to be a variation required by BECIL.

12.0 SCOPE AND EXTENT

12.1 SCOPE:- The general character and scope of the work is illustrated and defined by specification and by the signed Drawings. If the Contractor shall find any discrepancy in or divergence between the contract drawings and or the Contract bill shall immediately give to the Project Architect a written notice specifying the discrepancy or divergence and the Architect Consultants shall issue instruction in regard there to.

12.2 EXTENT: - The Contractor shall carry out and complete the work in every aspect in accordance with the Contract and with the direction of and to the reasonable satisfaction of the Architect Consultants and the Principles. The Architect, from time to time, may issue further drawings, and which are collectively referred to as Architect Consultants instructions. All such drawings and instruction shall be consistent with the contract document, true development thereof, and reasonable inferable there from.

12.3 The Contractor shall not without the written consent of BECIL, assign this contract or sublet any portion of the work failing which BECIL may serve a notice in writing rescinding the contract where upon the security deposit may be forfeited.

13.0 ARCHITECT CONSULTANTSS /BECIL REPRESENTATIVE INSTRUCTIONS

13.1 If within seven days after receipt of written notice from the BECIL. Representative/Architect Consultants to the Contractor, required compliance to rectify, reconstruct or replace any defective work or that the work is being performed in an inefficient or otherwise improper or unwork manlike manner shall omit to comply, then BECIL may employ and pay other person to execute any work what so ever at contractors risk, cost and earnest money, security deposit and performance guarantee are liable to be forfeited and shall be absolutely at deposable of BECIL.

13.2 All instruction issued by the BECIL Representative shall be in writing. Any instruction issued orally shall be of immediate effect but shall be confirmed in writing by the Contractor within seven days and if not dissented by the, BECIL Representative the Contractors confirmation shall take effect as from the expiry of the said period of seven days.

14.0 FACILITIES AND COOPERATION

In case of the work indicated on the drawing but not included in the bill of quantities, the Contractor shall provide necessary facilities and cooperation for execution such work including all cutting filling or patching of his work that may be required or execute such work so as to receive the work of other contractor shown upon or reasonably implied by the drawings and specification for the completed structure, and he shall make good. The Architect consultants/ BECIL Representative may direct, any cost caused by the defective or ill- timed work to be borne by the party responsible thereof.

15.0 SETTING OUT

The Architect consultants/ BECIL Representative, after consulting the Architect shall determine any lines and levels which may be required for the execution of the work and shall furnish to the Contractor by way of accurately dimensioned drawing such information shall enable the Contractor to set out the work at ground level. The Contractor shall set out the level of work and shall be responsible for the accuracy of the same. No payment shall be made for such layout at any level.

16.0 SITE VISIT

Before tendering, the Contractor shall be deemed to have examined the Site and satisfied himself as to the nature of the existing road or other means of communication and site constraints if any.

17.0 POSSESSION

The Contractor shall be allowed admittance to the site 7 days before the date of Submitted by (Tenderer) For BECIL.

Commencement stated in the letter and shall regularly proceeds with and complete the same on or before the date of completion stated in the schedule F, nevertheless to the provision for the extension of time granted as per provisions of contract.

17.1 TREASURES :

Any Treasures, coins, objects of antiquity, which may be found at the site shall be handed over to the principals.

18.0 SAMPLES

18.1 BECIL representative shall check in consultation with the Architect Consultants, approve samples, with reasonable promptness for being in conformity with the design concept of the project and for being in confirmation in the contract document. The work shall be carried out in accordance with the approved samples and shop drawings given by the Architect Consultants.

18.2 Random samples of concrete shall be taken from the site as per normal Civil Engineering practice and tested in a lab approved by the Architect consultants. Necessary equipment shall be provided by the contractor and such charges for the test shall be borne by the contractor.

19.0 PROGRESS CHART

The Contractor shall prepare PERT chart/ Activity chart and submit the same for approval of BECIL/Architect consultants. He should also submit weekly progress report to BECIL to ensure conformity with pert chart / activity chart.

20.0 ACCESS TO THE WORK

The Project Architect and his representatives and the Principles (BECIL) and their representatives shall at all reasonable time have access to the works and to the workshops or other places where work or fabrication is being prepared for the Contract.

21.0 BECIL STATUS AND DECISIONS

- 21.1** The term BECIL Representative means the person appointed or nominated by BECIL who shall supervise and be in charge of the work at site. The work shall be subject to the guidance of the Architect Consultants and under control and direction of the Principles BECIL.
- 21.2** M/s Environment Design Consultants (EDC) shall be the representative of BECIL during the construction period. Their representative shall periodically visit the site; familiarize himself generally with the progress and the quality of the work to determine in general if the work is proceeding in accordance with contract document.
- 21.3** The contractor shall, on receipt of the order in writing of the Architect consultants/BECIL Representative (whose decision is final and binding on the contractor) suspend the progress of the works or any part thereof for such time and in such manner as the Architect consultants/BECIL Representative may consider necessary so as not to cause any damage or injury to the work already done or endanger the safety thereof for any of the following reasons:
- (a) On account of any default on the part of the contractor or;
 - (b) For proper execution of the works or part thereof for reasons other than the default of the contractor or;
 - (c) For safety of the works or part thereof
- The contractor shall, during such suspension, properly protect and secure the works to the extent necessary and carry out instructions given in that on behalf of the Architect consultants/BECIL Representative
- 21.4** Decisions: The Architect Consultants shall within a reasonable time give decision on all claims of the Contractor and all other matters relating to the execution and progress of the work. The Architect Consultants may in consultation with the principles i.e. BECIL so desire to find it necessary, and from time to time issue further drawings, details and/ or written instructions, written directions and written explanation.
- 21.5** Dismissal: The contractor shall on the written instruction of the Architect consultants/ Principle BECIL immediately dismiss from the work any person employed thereon by him who may be in the opinion of the Architect consultants and/ or the Principles be incompetent. The same Person may not be employed on the work without the permission of the BECIL Representative or the Principles as the case may be.

22.0 CONTRACTORS FIELD ORGANISATION AND EQUIPMENT

Equipment: The Contractor shall provide and install all necessary hoists, ladders, Scaffolding, tools, plants, motors, pumps, all transport for labour and plant necessary for the proper carrying out execution and completion of the work to the satisfaction of the BECIL Representative/Principles.

23.0 DEVIATIONS/VARIATIONS EXTENT AND PRICING

23.1 In exceptional cases, the Architect consultants shall have power to make alteration in, omission from, addition to, or substitution for the original specification, drawings, designs and instruction that may appear to him to be necessary or advisable during the progress of the work, and to omit a part of the works in case of non-availability of a portion of the site or for any other reasons and contractor shall be bound to carry out the works in accordance with any instructions given to him in writing signed by the Architect consultants and such alterations, omission, additions or substitutions shall form part of the contract as if originally provided therein and any altered, additional or substituted work which the contractor may be directed to do in the manner specified above as the part of the works, shall be carried out by the contractor on the same condition in all respects including price on which he agreed to do the main work except as hereafter provided.

23.2 The time of completion of the work shall, in the event of deviation resulting, additional cost over the tender value sum being ordered, be extended, if requested by the contractor, as follows:

In the proportion which the additional cost of the altered additional or substituted work, bears to the original tender value plus.

23.3 DEVIATION EXTRA ITEMS AND PRICING

In the case of extra item(s) the contractor may within fifteen days of receipt of the work order and or occurrence of the item(s) claim rates, supported by the proper analysis, for the work and the Architect consultants/BECIL Representative shall within 15 days of the receipt of the claim supported by analysis after giving consideration to the analysis of the rates submitted by the contractor, determine the rate on the basis of the market rates and the contractor shall be paid in accordance with the rates so determined.

23.4 DEVIATION, SUBSTITUTED ITEM PRICING

In case of substituted items, the rate for the agreement item (to be substituted) and substituted item shall also be determined in the manner as mentioned in the aforesaid para.

- a) If the market rate for the substituted item so determined is more than the market rate of the agreement item (to be substituted) the rate payable to the contractor for the substituted item shall be the rate for the agreement item (to be substituted) so increased to the extent of the difference between the market rate of substituted item and agreement item (to be substituted).
- b) If the market rate for the substituted item so determined is less than the market rate of the agreement item (to be substituted) the rate payable to the contractor for the substituted shall be the rate for the agreement item (to be substituted) so decreased to the extent of the

difference between the market rate of substituted item and agreement item (to be substituted).

24.0 DEVIATION, DEVIATED QUANTITIES, PRICING

24.1 In the case of contract item, substituted item, contract cum substituted item, which exceeds the limits of quantities as given in schedule 'F' the contractor may within fifteen days of receipt of order or occurrence of the excess, claim revision of the rate, supported by proper analysis, the work in excess of the above mentioned limits, provided that if the rates so claimed are in excess of the rate specified in the schedule of quantities the Architect consultants/BECIL Representative shall within 15 days of receipt of the claims supported by analysis, after giving consideration to the analysis of the rate submitted by the contractor, determine the rate on the basis of market rates and the contractor shall be paid in accordance with rates so determined.

24.2 The provisions of the preceding paragraph shall also apply to the decrease in the rates of items for the work in excess of the limits laid down in Schedule F", and the Architect consultants/BECIL Representative shall after giving notice to the contractor within 10 days of occurrence of the excess and after taking into consideration any reply received from him within fifteen days of the receipt of the notice, revise the rates for the work in question within 15 days of the expiry of the said period of fifteen days having regard to the market rates.

24.3 The contractor shall send to the Architect consultants/BECIL Representative once every months an up to date account giving complete details of all claims for addition payments to which the contractor may consider himself entitled and of all additional work ordered by the Architect consultants/BECIL Representative which he has executed during the preceding period failing which the contractor shall be deemed to have waived his right. However, the CMD BECIL may authorize consideration of such claims on merits.

24.4 Any operation incidental to or necessarily has to be in contemplation of tender while filling tender, or necessary for proper execution of the item included in the Schedule of quantities or in the schedule of rates mentioned above, whether or not, specifically indicated in the description of the item and the relevant specifications, shall be deemed to be included in the rates quoted by the Tenderer or the rate given in the said schedule of tendered rates, as the case may be. Nothing extra shall be admissible for such operation.

25.0 WHEN CONTRACT CAN BE DETERMINED

25.1 Subject to other provisions contained in the clause, the Architect consultants/BECIL Representative may, without prejudice to his any other rights or remedy against the contractor in respect of any delay, inferior workmanship, any claims for damages and/or any other provision of this Otherwise, and whether the date of completion has or has not elapsed, by notice in writing absolutely determine the contract in any of the following cases:

- (a) If the contractor, having been given by the Architect consultants/BECIL Representative notice in writing to rectify, reconstruct or replace any defective work or that the work is

- being performed in an inefficient or otherwise improper or un workmanlike manner shall omit to comply with the requirement of such notice for a period of seven days thereafter.
- (b) If the contractor has, without reasonable cause, suspended the progress of the work or has failed to proceed with the work with due diligence so that in the opinion of the Architect consultants/BECIL Representative (which shall be final and binding) he will be unable to secure completion of the work by the date for completion and continues to do so after a notice in writing of seven days from the Architect consultants/BECIL Representative.
 - (c) If the contractor fails to complete the work within the stipulated date or items of work with individual date of completion, if any stipulated, on or before such date(s) of completion and does not complete them within the period specified in a notice given in writing in that behalf by the Architect consultants/BECIL Representative.
 - (d) If the contractor persistently neglects to carry out his obligations under the Contract and/ or commits default in complying with any of the terms and condition of the Contract and does not remedy it or take effective steps to remedy it within 7days after a notice in writing is given to him in that behalf by the Architect consultants/BECIL Representative.
 - (e) If the contractor shall offer or given or agree to give to any person in BECIL service or to any other person on his behalf any gift or consideration of any kind as an inducement or reward for doing or forbearing to do or for having done or forborne to do any act in relation to the obtaining or execution of this or any other contract for BECIL.
 - (f) If the contractor shall enter into a contract with BECIL in connection with which commission has been paid or agreed to be paid by him or to his knowledge, unless the particulars of any such commission and the terms of payment thereof, have been previously disclosed in writing to the Architect consultants/BECIL Representative.
 - (g) If the contractor shall obtain a contract with BECIL as a result of wrong tendering or other non bonafide methods of competitive tendering.
 - (h) If the contractor being an individual, or if a firm, insolvent or have a receiving order or for administration of his estate made against him or shall take any proceedings for liquidation for composition (other than a voluntary liquidation for the purpose of amalgamation or reconstruction)under any insolvency Act for the time being in force or make any conveyance or assignment of his effects or composition or arrangement for the benefit of his creditors or purport so to do, or if any application be made under any insolvency Act for the time being in force to make any conveyance or assignment of his effects or composition or arrangement for the benefit of his creditors or purport so to do, or if any application be made under any insolvency Act for the time being force for the sequestration of his estate or if a trust deed be executed by him for benefit of his creditors .
 - (i) If the contractor being a company shall pass a resolution or the court shall make an order that the company shall be wound up or if a receiver or a manager or behalf of a creditor shall be appointed or if circumstances shall arise which entitle the court or the creditor to appoint a receiver or a manager or which entitle the court to make a winding up order.
 - (j) If the contractor shall suffer an execution being levied on his goods and allow it to be continued for a period of 21 days.

- (k) If the contractor assigns, transfers, sublets (engagement of labour on a piece-work basis or of labour with materials not to be incorporated in the work, shall not be deemed to be subletting) or otherwise parts with or attempts to assign, transfer sublet or otherwise parts with the entire works or any portion thereof without the prior written approval of the Architect consultants/BECIL Representative.
- (l) If the work is not started by the contractor within 7 days of the award of work. When the contractor has made himself liable for action under any of the cases aforesaid, the Architect consultants/BECIL Representative shall have powers:
- (a) To determine the contract as aforesaid (of which termination notice in writing to the contractor under the hand of the Architect consultants/BECIL Representative shall be conclusive evidence). Upon such determine, the Earnest Money Deposit, Security Deposit already recovered and Performance Guarantee under the contract shall be liable to be forfeited and shall be absolutely at the disposal of BECIL.
 - (b) After giving notice to the contractor to measure up the work of the contractor and to take such whole, or the balance or part thereof, as shall be un-executed out of his hands and give it to another contractor to complete the work. The contractor, whose contract is determined as above, shall not be allowed to participate in the tendering process for the balance work.
 - (c) In the event of above courses being adopted by the Architect consultants/BECIL Representative, the contractor shall have no claim to compensation for any loss sustained by him by reasons of his having purchased or procured any materials or entered into any engagements or made any advances on account or with a view to the execution of the work or the performance of the contract. And in case action is taken under any of the provision aforesaid, the contractor shall not be entitled to recover or be paid any sum for any work thereof or actually performed under this contract unless and until the BECIL Representative has certified in writing the performance of such work and the value payable in respect thereof, and he shall only be entitled to be paid the value so certified.
 - (d) In case, the work cannot be started due to reasons not within the control of the Contractor within 7 days of the award of work, either party may close the contract. In such eventuality the Earnest Money Deposit and the Performance Guarantee of the contractor shall be refunded, but no payment on account of interest, loss of profit or damages etc. shall be payable at all.

26.0 Contractor liable to pay compensation even if action not taken under Clause - 25

- 26.1 In any case in which any of the powers conferred upon the Representative by the clause-25 thereof, shall have become exercisable and the same are not exercised, the non exercise thereof shall not constitute a waiver of any of the conditions hereof and such powers shall notwithstanding be exercisable in the event of any future case of default by contractor and the liability of the contractor for compensation shall remain unaffected. In the event of the BECIL Representative putting in force all or any of the powers vested in him under the preceding clause he may, if he so desires after giving a notice in writing to the contractor,

take possession of (or at the sole discretion of the BECIL Representative which shall be final and binding on the contractor) use as on hire (the amount of the hire money being also in the final determination of the Representative) of any tools, plant, materials, stores, in or upon the works, or the site thereof belonging to the contractor, or procured by the contractor and intended to be used for the execution of the work / or any part thereof, paying or allowing for the same in account at the contract rates, or in the case of these not being applicable, at current market rates to be certified by the BECIL Representative, whose certificate thereof shall be final , and binding on the contractor, clerk of the works, foreman or other authorized agent to remove such tools, plant, materials or stores from the premises (with in a tie not be specified in such notice) In the event of the contractor failing to comply with any such requisitions, the BECIL Representative may remove them at the contractors expense or sell them by auction or private sale on account of the contractor and his risk in all respect and the certificate of the BECIL Representative as to the expense of any such removal and the amount of the proceeds and expenses of any such sale shall be final and conclusive against the contractor.

27.0 Contractors cooperation with other contractors.

27.1 The contractor shall help & co-operate in work & installation the other contractors working on other Part / parts of the building under separate contract to align & keep appropriate levels, services, though Water supply, & electrical etc.The contractor shall jointly undertake testing of such services / work Required for successful completion of work to the satisfaction of the BECIL representative.

28.0 MEASUREMENT OF WORK DONE /CERTIFICATES AND PAYMENTS

28.1 Contractor's site in charge shall, except or otherwise provide, ascertain and determine by measurement the value in accordance with the contract of the work done. All measurement of items having financial value shall be entered in Measurement book and /or level field book so that a complete record is obtained of all works performed under the Contract.

28.2 At the period of interim certificate named in the Schedule F to this condition the BECIL Representative shall issue a certificate stating the amount due to the Contractor from the Principles and after concurrence by the Architect Consultants, the Contractor will be entitled to payment thereof, within the period for honoring certificate. Interim valuations shall be made whenever the BECIL Representative considers it to be necessary. Generally, the certificate shall be issued when the Contractor executes the net work costing Rs 7.5 lacs or equivalent or more.

28.3 The amount stated as due in an interim certificate shall be total value of the work properly executed and of the materials and goods delivered to or adjacent to the work for use thereon up to and including a date not less than seven days before the said certificate, less any amount which may be retained by the Principles and less any installment previously paid under this condition.

28.4 The principal shall retain 5% of the total value of the work done as security deposit, and be subject to the conditions agreed upon in respect thereof in the contract documents.

28.5 The Contractor shall be entitled to the payment of the final balance in accordance with the final certificate. This shall be issued in writing by the Project Architect/BECIL Representative at the expiry of the period referred to as the Defects Liability Period of

twelve months from the date of completion or as soon as after the expiry and all defects made good according to the true intent and meaning here of which ever shall last happen. No further claims shall be made by the contractor and these shall be deemed to have been waived and extinguished.

28.6 The measurement and valuation of the work shall be completed with in the period of final Valuation and measurement stated in the appendix to these conditions. The Contractor shall be supplied with the copy of the priced bill of valuation not later than the end of the said period and before the issue of final certificate.

28.7 Billing is to be done by the contractor in respect of the broadcasters through BECIL.

29.0 ADVANCES

Generally no advances shall be paid. However upon furnishing such request by the Contractor through BECIL Representative, secured advance upto 50% of the cost of raw materials may be made to the contractor for non-perishable, non fragile and noncombustible and are in accordance with the contract and which has been brought on the site in connection therewith and are adequately stored goods but which may have not at the time of advance been incorporated in the works.

When materials on account of which an advance has been made under this sub-clause are incorporated in the work, the amount of such advance shall be recovered / deducted from the next payment made under any of the clause or clauses of this contract.

30.0 CLAIMS FOR EXTRAS

When any instruction or decision given involves an extra amount or whereby the Contractor may plan to claim an extra amount it shall be the responsibility of the Contractor to inform the principles of the extra amount and get written authorization from the principles before proceeding with the work involved. The rates for such extra work or extra items shall be determined in accordance with the C.P.W.D system of Analysis of Rates and shall not be derived from agreed rates in this contract. The Architect Consultants decision regarding rates shall be final.

31.0 DEDUCTION FOR UNCORRECTED WORK

If the Project Architect deems it inexpedient to correct work damage or not done in accordance with the contract an equitable deduction from the contract price shall be made by the principles there of on the basis which is applicable for extra work/items as worked out by the Architect Consultants.

32.0 FLUCTUATIONS

The Contractor shall not claim any extra for fluctuation of price and the contract price shall not be subject to any rise for prices except as provided for especially in any clause in the Contract Document.

33.0 VARIATIONS

On signing upon the contract by both the parties, during execution the quantities may vary up to 50% of the superstructure quantities & 100% for the items below the plinth level, based on drawings.

34.0 INSPECTION TESTING AND RECTIFICATION OF DEFECTIVE WORK

As and when required by the principles or the BECIL Representative upon the advice of Architect Consultants, Contractor shall organize inspection of works at his cost to prove their soundness and efficiency. If after tests any work or portions of work are considered defective or unsound by the Principles or the BECIL Representative /Architect Consultants, the Contractor shall remove the defective work from the site, or pull down and re-execute the works at his own cost to the satisfaction of Architect consultants/BECIL Representative and the Principles. The Contractor shall furnish promptly, without additional charges, all reasonable facilities and labour necessary for the safe and convenient inspection and test that may be required by the Project Architect or Principles.

35.0 POSSESSION, COMPLETION, AND POSTPONMENT

- 35.1** On the date of commencement stated in the appendix to these condition possession of the site shall be given to the Contractor who shall, there upon, begin the work regularly and diligently proceed with the same and he shall complete the same on or before the stipulated date for or in accordance with provisions of extension of time contained in the conditions.
- 35.2** BECIL Representative may issue instructions in regard to the postponement of any work to be executed under the provisions of this contract. BECIL reserves the right of constructing any part of the building themselves.

36.0 EXTENSION

Upon it becoming reasonably apparent that the progress of the work is delayed, the Contractor shall forthwith, give written notice of the cause of the delay to the Principles that the completion of the work is likely to be or has been delayed beyond any extended time previously fixed under the clauses. The Architect Consultants may recommend extension of time to principles for such period for which delay occurred for reasons beyond the control of Contractors.

37.0 TERMINATION / FORECLOSURE OF CONTRACT

- 37.1** After the due process of the CPWD and incase in the opinion of BECIL, any of the clauses are violated by the Contractor. The contract can be determined by BECIL and work executed at the risk and cost of Contractor.
- 37.2** In the event of the contract being determined or rescinded (of which termination or rescission notice in writing to the contractor under the hand of the BECIL Representative shall be conclusive evidence). Upon such determination or rescission, the Earnest Money Deposit,

Submitted by (Tenderer)

For BECIL.

Security Deposit already recovered and Performance Guarantee under the contract shall be liable to be forfeited and shall be absolutely at the disposal of BECIL.

- 37.3** Foreclosure of Contract: At any time after acceptance of the tender, BECIL shall decide to abandon or reduce the scope of works for any reason whatsoever and hence not require the whole or any part of the works to be carried out, The BECIL Representative after consulting Architect consultants gives a notice in writing to that effect to the contractor and the contractor shall act accordingly in the matter. The contractor shall have no claim to any payment of compensation or otherwise whatsoever, on account of any profit or advantage which he might have derived from the execution of the works in full but which he did not derive in consequence of the foreclosure of the whole or part of the works. The contractor shall, if required by BECIL Representative furnish to him books of account, wage books, time sheets and other relevant documents and evidence as may be necessary to enable him to certify any reasonable amount payable.

38.0 ARBITRATION AND JURISDICTION

In case of any dispute, the principles shall appoint in consultation and agreement with the Contractor an Architect / Engineer of repute in Delhi (India) as Arbitrator whose decision shall be final and binding on both the parties i.e. the principal and the Contractors.

However, the jurisdiction of the Delhi High Court shall be accepted by both parties incase reference of dispute is made to a court.

39.0 WORKMANSHIP

All workmanship shall be of best trade practices and contractor shall immediately remove from the work the workmanship which in the opinion of the Principals or their representative are defective or unsuitable and shall substitute proper workmanship at his own cost.

N.B: In case any situation or dispute is not covered by any of the clauses stated above & General Conditions of Contract in this contract document provisions of clauses contained on form 8 of CPWD shall be applied.

SCHEDULE 'F'

REFERENCE TO GENERAL CONDITIONS OF CONTRACT:

NAME OF WORK: MODIFICATIONS / ADDITIONS / ALTERATIONS IN EXISTING CTI BUILDING LOCATED AT BAREILLY (UP) ON BEHALF OF PRIVATE BROADCASTERS FOR FM PHASE - III (BATCH – 1).

- 1 (i) Earnest money: 2% of Estimated cost
- (ii) Performance Guarantee: 5% of tendered value
- (iii) Security Deposit: 5% of tendered value deductions from all interim bills
- Officer inviting tender: CMD BECIL

Maximum percentage for quantity of items of work to be executed beyond which rates are to be determined in accordance with clause 24 :

100% for items of work in foundations
50% for work items of work in superstructure
100 % for items of Electrical Works

2. Definitions:

- 2(a) BECIL Representative: Representative of BECIL (Nominated by CMD of BECIL)
- 2(b) Contractor site in charge Contractor site in-charge responsible for the construction activity at site.

2(c) Accepting AuthorityCMD BECIL

2 (d) Percentage on cost of material & labour to cover all overheads and profits15%

2 (e) Standard Schedule of Rates: CPWD Scheduled of Rate DSR 2014

2 (f) Department:BECIL

3. Time allowed for submission of performance guarantee from the date of issue of letter of acceptance , in days.....07 days

4 Authority for fixing compensation:CMD BECIL

Submitted by (Tenderer)

For BECIL.

5. Number of days from the date of issue of letter of acceptance for reckoning date of start --- 07 days
6. Time allowed for the execution of work --- 03 Months
7. Defects Liability Period --- 12 Months
8. Period of final Measurement --- 01 Month
9. Agreed liquidated damageRs 5,000/- (Rs Five Thousand only) per day to max of 10 % (Penalty for delay) of the contract value
10. Limit of Retention fund.....5 % performance guarantee + (Plus) Security deposit of 5% of Tendered value
11. Period of honoring certificate --- 30 days.
12. Authority to give fair and reasonable extension of time for completion of work --- CMD BECIL
13. Gross work to be done together with net Payment /adjustment of advances for material Collected, if any since the last such payment for being eligible to interim payment. --- Rs. 7.50 Lakhs
14. Specifications to be followed for execution of work: C.P.W.D specifications (Vol. - I to Vol – VI along with up to date Correction slips.)
15. Nearest material for which all India whole sale price index is to be followed:
TMT steel – mild steel
Cement (OPC) /PPC cement .
16. Competent Authority for deciding reduced rates --- CMD BECIL
17. List of mandatory machinery, tools & plants to be deployed by the contractor at site.
- i. C.Conc. Mixer
 - ii. Vibrator
 - iii. Pump Sets

18. Requirement of Technical Representative (s) and recovery Rate

S.No	Minimum Qualification of Technical Representative	Discipline	Description Principal Technical/ Technical Representative	Minimum Experience	Number	Rate at Which recovery shall be made from the contractor in the event of not fulfilling provision
1.	Diploma in Engineering	Civil Engg.	Site Engineer	3Yrs.	1	Rs.15,000.00 P.M.

APPENDIX - 1

MODIFICATIONS / ADDITIONS / ALTERATIONS IN EXISTING CTI BUILDING LOCATED AT BAREILLY (UP) ON BEHALF OF PRIVATE BROADCASTERS FOR FM PHASE - III (BATCH – 1)

1. All works shall be carried in accordance with the CPWD specifications updated with correction slips
2. All reinforcement steel shall be T.M.T and structural steel used shall be as per relevant ISI standards and as specified by the Architect consultants.
3. The work shall be carried out in accordance with the relevant codes.
4. Cement used shall be as per ISI standards and of category 43 grade ordinary Portland cement unless specified otherwise.
5. All shuttering used in the beams, slabs or columns shall be steel or waterproof plywood.
6. Puff panels used will be 100mm thick sandwich insulated panels for external walls, 50mm thick insulated sandwich panels for roof as specified in the BOQ.
7. The puff panel will have following 'U' values
50mm thick panels - U- 0.43w/m² deg. C
100mm thick panels - U- 0.22w/m² deg. C
8. All electrical cables fittings shall be ISI marked and of ISI standards.
9. All works shall be executed to relevant electrical codes.
10. Cables used shall be of one of the following makes :
 - a) RR Cables
 - b) Finolex
 - c) Havells
11. Sanitary ware shall be of one of the following makes :
 - a) Cera
 - b) Hindware
 - c) Parryware
12. All tile work for floor & walls shall be one of the following makes:
 - a) Kajaria
 - b) Nitco
 - c) Johnson
13. Plaster of Paris partitions or Gyp boards sheet shall be in :
 - a) Gypsum India
 - b) Lafarge
 - c) Gyproc (SAINT-GOBAIN)
 - d) India Gypsum

B O Q

FOR

MODIFICATIONS / ADDITIONS / ALTERATIONS IN EXISTING
CTI BUILDING LOCATED AT BAREILLY (UP) ON BEHALF OF
PRIVATE BROADCASTERS FOR FM PHASE - III (BATCH – 1)

NOTE - QUOTED RATES OF ALL ITEMS SHALL BE
INCLUSIVE OF ALL TAXES

SECTION -A (BOQ for Modifications / Additions / Alterations in existing CTI building located at BAREILLY (UP) on behalf of Private Broadcasters for FM Phase - III (Batch – 1) - ----New work (CIVIL)

S.No	Description	Unit	Qty	Rate	Amount
1	<u>SITE CLEARENCE</u>				
1.1	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30cm measured at a height of 1m above ground level and removal of rubbish up to a distance of 50m outside the periphery of the area cleared.	100 sq.mt	0.86		
2	<u>DISMANTLING & DEMOLISHING</u>				
2.1	Demolishing brick work manually/ by mechanical means, including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of BECIL representative.				
	(a) In Cement Mortar	cmt	4.00		
2.2	Removing mortar from bricks and cleaning bricks including stacking within a lead of 50 m (stacks of cleaned bricks shall be measured)				
(a)	From brick work in cement mortar	1000 nos.	0.86		
2.3	Dismantling doors, windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead:				
(a)	Of area 3 sq. metres and below.	nos.	2.00		
2.4	Dismantling C.I. or PVC rain water pipe with fittings and clamps including stacking the material within 50 metres lead:				
(a)	100mm dia pipe	rmt.	3.00		
2.5	Dismantling of existing puff panels in roof and walls manually / by mechanical including stacking with 50 meter 50 meters lead as per direction of BECIL representative:	Sq.mt	5.00		
2.6	Dismantling of cement concrete platform along with base concrete etc. including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead:	cmt.	1.00		
2.7	Disposal of building rubbish / malba / similar unserviceable, waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by BECIL representative, beyond 50 m initial lead, for all leads including all lifts involved.	cmt	2.50		

2.8	Securing all openings during demolishing or dismantling with plyboard partitions or corrugated GI sheet as directed by BECIL representative. Plastic sheets etc. to be used in roof and openings etc. to prevent ingress of rain/dust during construction activity	Sq.mt	3.00		
2.9	Dismantling grid ceiling or other hard board ceiling or partition walls including stacking of serviceable materials and disposal of unserviceable materials within 50 metres lead.	sq.mt	1.00		
2.10	Dismantling, stacking for possible re use within 50 metres lead, fencing, posts, gate, grill, railing or struts including all earth work and dismantling of concrete etc. in base of:				
(a)	MS angle, flat, Tee, bar or pipe etc.	sq.mt	26.00		
2.11	Dismantling tile work in floors laid in cement mortar including stacking of material within 50 metres lead.				
(a)	For thickness of tiles 10 mm	Sq.mt	1.00		
2.12	Demolishing R.C.C. work manually/ by mechanical means, including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of BECIL representative.	cmt	1.00		
3	<u>EARTH WORK</u>				
3.1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including disposal of excavated earth upto 50 m and lift upto 1.5 m, disposed soil to be levelled and neatly dressed. All kinds of soil	100 sq.mt	0.45		
3.2	Earth work in excavation by mechanical means, (Hydraulic excavator) /manual means over areas (exceeding 30 cm in depth. 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift up to 1.5m, disposed earth to be levelled and neatly dressed. All kinds of soil.	cmt	22.00		
3.3	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m.				
(a)	All kinds of soil.	cmt	6.50		

3.4	Filling with earth brought from outside (excluding rock) in plinth/trenches in layers (each layer should not exceed 15 cm), with intermediate layer of compacted earth (Soil density of 98%) after every four layers of / ramming and watering, all complete as per drawing and direction of BECIL representative.	cmt	5.00		
3.5	Laying, spreading and compacting of 63mm to 45mm size stone aggregate to form 150 mm thick hard core and preparing surface complete.	cmt	8.00		
3.6	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.				
(a)	All kinds of soil.	cmt	9.00		
3.7	Excavating trenches of required width for pipes, cables, etc. including excavation for sockets, and dressing of sides, ramming of bottoms, depth upto 1.5 m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil:				
(a)	Pipes, cables etc. exceeding 100 mm dia but not exceeding 300 mm	rmt.	5.00		
4	<u>CONCRETE WORK</u>				
4.1	Providing and laying in position cement concrete of specified grade as per drawing excluding the cost of centering & shuttering. All work up to plinth level.				
(a)	1:1½:3 (1 Cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size)	cmt	1.00		
(b)	1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	cmt	4.00		
(c)	1:4:8(1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	cmt	5.50		
4.2	Providing and laying in position cement concrete of specified grade as per drawing excluding the cost of centering & shuttering, All work above plinth level.				
(a)	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	cmt	1.50		
(b)	1:1½:3 (1 Cement: 1½ coarse sand: 3 graded stone aggregate 20 mm nominal size)	cmt	1.00		

5	<u>FORM WORK</u>				
5.1	Centering and shuttering including strutting propping etc. and removal of form work of up to plinth				
(a)	Foundation, footings, bases of columns etc.	sq.mt	30.00		
5.2	Centering and shuttering including strutting propping etc. and removal of form work above plinth level for:				
(a)	Suspended floors, roofs, landings, projections, balconies, and access platform.	sq.mt	14.00		
(b)	Lintel, Beam, Plinth beam, columns, arches, piers, pillars, posts and struts.	sq.mt	3.24		
6	<u>DAMP PROOF COURSE</u>				
6.1	Providing and laying damp-proof course 40 mm thick with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 12.5 mm nominal size with water proofing compound of make Dr. FIXIT or CICO as per manufacturer's specifications	sq.mt	6.00		
7	<u>R.C.C</u>				
7.1	Reinforced cement concrete work in footing, pedestal and column upto plinth level excluding the cost of centering, shuttering, finishing and reinforcement.				
(a)	1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	cmt	3.50		
(b)	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	cmt	0.50		
7.2	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, band, abutments, posts and struts etc. above plinth level excluding the cost of centering, shuttering, finishing and reinforcement.				
(a)	1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	cmt	1.00		
(b)	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	cmt	0.50		
7.3	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, Coping, bands, plain window sills, staircases above plinth level excluding the cost of centering shuttering.				
(a)	1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	cmt	1.00		

(b)	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	cmt	0.50		
8	<u>BRICK WORK</u>				
8.1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 75 in foundation and plinth in:				
(a)	Cement mortar 1:6 (1 cement : 6 coarse sand)	cmt	8.32		
8.2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 75 above plinth level in all shapes and sizes in :				
(a)	Cement mortar 1:6 (1 cement : 6 coarse sand)	cmt	7.50		
8.3	Half brick masonry with First Class bricks of class designation 75 above plinth level including 2 nos. 6 mm dia M.S bars at every third course:				
(a)	cement mortar 1:4 (1 cement : 4 coarse sand)	sq.mt	37.00		
9	<u>STEEL REINFORCEMENT</u>				
9.1	Steel Reinforcement for R.C.C work including Straightening, cutting, bending, placing in position and binding all complete up to plinth:				
(a)	Thermo-Mechanically Treated bars	kg	400.00		
9.2	Steel Reinforcement for R.C.C work including Straightening, cutting, bending, placing in position and binding all complete above plinth:				
(a)	Thermo-Mechanically Treated bars	kg	174.00		
10	<u>STRUCTURAL STEEL</u>				
10.1	Structural steel work riveted, bolted or welded in built up sections, single section, frame work, including connecting plate cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.				
(a)	In frames, guard bar, ladder, railings, brackets, gates, truss, post and similar works.	Kg	1812.00		
11	<u>CEMENT PLASTER</u>				
11.1	15 mm internal cement plaster of mix: 1:6 (1 cement: 6 fine sand).	sq.mt	45.00		
11.2	18 mm cement plaster in two coats under layer 12 mm thick cement plaster 1:5 (1 cement : 5 coarse sand) finished with a top layer 6 mm thick cement plaster 1:6 (1 cement : 6 fine sand).	sq.mt	45.00		
12	<u>FLOORING</u>				

12.1	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS : 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), including grouting the joints with white cement and matching pigments etc., complete. (Basic rate of tile Rs 600/- per sqm)	sq.mt	53.00		
12.2	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, 100 mm high over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), including grouting the joint with white cement & matching pigments etc. complete. (Basic rate of tile Rs 600/- per sqm)	sq.mt	4.00		
12.3	Making floor trench required for cables etc. inside the building constructed of half brick work in bottom include a lid in 25mm thick block board of ISI specification covering the trench with floor tiles fixed to the lid with araldite or any other approved fixative. Each lid shall not be more than 300x1200 mm and fixed within frame of MS angle 25mm x25mm as per drawing.	rmt.	24.00		
12.4	52 mm thick cement concrete flooring under layer 40 mm thick cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) and top layer 12 mm thick cement concrete consisting of mix 1:2 (1 cement : 2 graded stone aggregate 6 mm nominal size) by volume, This includes cost of cement slurry, but excluding the cost of nosing of steps etc. complete.	sq.mt	13.00		
13	<u>DOORS AND WINDOWS</u>				
13.1	Providing and fixing aluminum work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminum sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including	Sq.mt	2.88		

	cleat angle, Aluminum snap beading for glazing / paneling, C.P. brass / stainless steel screws, dash fasteners all complete as per architectural drawings and the directions of BECIL representative. (Glazing and paneling to be paid for separately). Anodized aluminum (anodized transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15). For fixed portion.				
13.1.1	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required including fittings etc.				
(a)	Anodized aluminum (anodized transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	Sq.mt	5.70		
13.2	Providing and fixing glazing in aluminum door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of BECIL representative.				
(a)	With float glass panes of 5.50 mm thickness	sq.mt	6.31		
13.3	Providing and fixing double action hydraulic floor spring of approved brand and manufacture conforming to IS : 6315, having brand logo embossed on the body / plate with double spring mechanism and door weight upto 125 kg, for doors, including cost of cutting floors, embedding in floors as required and making good the same matching to the existing floor finishing and cover plates with brass pivot and single piece M.S. sheet outer box with slide plate etc. complete as per the direction of BECIL representative.				
(a)	With stainless steel cover plate minimum 1.25 mm thickness	each	2.00		
13.4	Filling the gap in between aluminum frame & adjacent RCC/ Brick/ Stone work by providing weather silicon sealant over backer rod of approved quality as per architectural drawings and direction of BECIL representative complete.				
(a)	Up to 5mm depth and 5 mm width	Rmt.	32.00		
13.5	Providing and fixing ISI marked anodized handles (anodic coating not less than grade AC 10 per IS:1868) transparent or Dyed to require colour or shade with necessary screw etc. complete. 250 X 63 X 4 mm as per direction of BECIL representative.	each	8.00		

13.6	Providing and fixing bright finished brass 100 mm mortice lock with 6 levers with necessary screw etc. complete (best make of approved quality).	each	2.00		
14	<u>INTERIOR FINISHING</u>				
14.1	Surface painting with Synthetic enamel paint of approved brand and manufacture, having VOC (Volatile Organic Compound) content less than 150 gm/litre (for truss and purlins) in Two coats	sq.mt	90.00		
14.2	Wall/ ceiling painting in two and more coats on new work with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour the wall surface shall be prepared with one coat of water thinnable cement primer of approved brand and manufacture having VOC content less than 50 grams/litr.	sq.mt	156.62		
14.3	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content.				
(a)	The surface shall be prepared with ready mixed red oxide zinc chromatic on steel / iron works having VOC content less than 250 grams/ litre	sq.mt	10.00		
15	<u>EXTERIOR FINISHING</u>				
15.1	Finishing walls with Acrylic Smooth exterior paint of required shade.				
(a)	New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	sq.mt	67.11		
16	<u>CONCRETE PAVERS</u>				
16.1	Providing and laying factory made coloured chamfered edge Cement Concrete paver blocks of required strength, thickness & size/shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of fine sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with jamuna sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand in footpath, parks, lawns, drive ways or light traffic parking etc. complete as per manufacturer's specifications & direction of BECIL representative 80mm thick	sq.mt	28.00		

	C.C. paver block of M-30grade with approved colour, design & pattern.				
17	<u>PUF PANEL</u>				
17.1	Providing and fixing PUF insulated sandwich panels for roof Having top profile sheet with 28-30mm crust hight at 195-200mm pitch, inner liner tray and PUF Insulation between not less than 50 mm thick and width 980mm. Panel shall have 0.50mm thick precoated GI sheet on both side of polyurethane foam confirming to IS 12436:1988 with standard profile with tongue & groove arrangement. The Precoated sheet shall be of minimum 240 mpa steel grade confirming to IS 14246:1995 and shall have zinc coating of minimum 120 gsm as per IS:277:1992, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 20 micron. The PPGI sheet shall have plastic protective guard film of minimum 25 microns to avoid scratches while transportation. The PU foam shall be self-extinguishing, fire retardant type having minimum density of 40 Kg/cum (+,-2 Kgs) including CFC Free panel should be GRIHA Certified. The panels shall be fixed to the steel frame structure with minimum 5 mm thick self tapping GI screws with EPDM seal of required length and nos. with minimum spacing of 300 mm c/c assembly/ the cost shall include ridge, soffit junctions & flashings as specified puff panel makers. Refer appendix-1	sq.mt	60.00		
17.2	Providing and fixing PUF insulated sandwich panels for walls of total thickness not less than 100mm and width 1.0 m having tongue and groove edge finish with camlock arrangement (as per manufacturer detail). Panel shall have 0.5mm thick precoated GI sheet on both side of polyurethane foam confirming to IS 12436:1988. The Precoated sheet shall be of minimum 240 mpa steel grade confirming to IS 14246:1995 and shall have zinc coating of minimum 120 gsm as per IS:277:1992, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 20 micron. The PPGI sheet shall have plastic protective guard film of minimum 25 microns to avoid scratches while transportation. The PU foam shall be self-extinguishing, fire retardant type having minimum density of 40 Kg/cum (+,-2 Kgs) including CFC Free panel should be				

	GRIHA Certified. The panels shall be fixed to the steel frame structure with minimum 5 mm thick self tapping GI screws of required length and nos. with minimum spacing of 300 mm c/c Refer appendix-1				
(a)	100mm PUFF panel external wall	sq.mt	55.00		
18	<u>GUTTER</u>				
18.1	Providing and fixing precoated galvanized steel sheet roofing accessories 0.50 mm (+ 0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 20 microns using self drilling/ self tapping screws, including ms flat flashing etc. to manufacture specification all complete: Gutter (600mm overall girth)	rmt.	9.00		
19	<u>FALSE CEILING</u>				
19.1	Providing and fixing 12mm gyp board false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall	sq.mt	53.00		

	screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes , finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cut outs made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the BECIL representative but excluding the cost of painting.				
19.2	Providing and fixing 12mm gyp board wall panelling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 , including fixing of gypsum board to wall section with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes , finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for doors, windows, cable tray, any holes/slots for electrical cables etc. cut outs made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the BECIL representative but excluding the cost of painting. This shall include securing, fixing of G.I concealed metal boxes, PVC conduits and cut outs in gypsum board to take modular plates/switches as per direction of BECIL representative.				
(a)	40mm overall thickness gypsum board lining to inside of puf panel with 12.5 mm thick single skin tapered edged plain Gypsum board conforming to IS: 2095: part I.	sq.mt	90.00		
20	<u>FENCING</u>				
(a)	Supplying & fixing of M.S Angle/MS T post & strut of required size with M.S angle welded & grouted in concrete.	kg.	750.00		
21	<u>FIRE EXTINGUISHERS</u>				

21.1	S&I of ISI marked Co2 type 4.5 Kg. capacity Fire extinguisher.	each	1.00		
22	Providing and fixing colour coated 0.5 mm Galvanized sheet of approved profile over the door & windows in the required width & protruding out 500 mm from wall panel. the canopy will be moulded at top & both vertical sides and will have all joints sealed with silicon with slope to drawings, complete with all fixtures, flashing, SS screws etc. Structural support system for such will be paid separately				
(a)	New canopy	Sq.mt.	3.20		
	TOTAL				

SECTION -A (BOQ for Modifications / Additions / Alterations in existing CTI building located at BAREILLY (UP) on behalf of Private Broadcasters for FM Phase - III (Batch – 1) -----New work (Electrical)

S.No	Description	Unit	Qty	Rate	Amount
1	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FR PVC insulated copper conductor single core cable in surface / recessed PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FR PVC insulated copper conductor single core cable etc as required. (Anchor Roma make or Havells)	Point	9.00		
2	Wiring for light/ power plug with 2X4 sq. mm FR PVC insulated copper conductor single core cable steel in surface/ recessed conduit along with 1 No 4 sq. mm FR PVC insulated copper conductor single core cable for loop earthing as required.	Rmt.	175.00		
3	S/F 15/16 Amp plate type switch along with 3 pin 15/16 Amp socket outlet on plate complete i/c modular box as required (Anchor Roma make or Havells)	Nos.	5.00		
4	Wiring for circuit wiring in PVC insulated copper conductor cable in surface/ recessed PVC conduit as required				
(a)	3x1.5 Sqmm	Rmt.	100.00		
(b)	3x2.5 Sqmm	Rmt.	70.00		
(c)	3x4.0 sqmm	Rmt.	65.00		
(d)	4x4.0 sqmm	Rmt.	50.00		
5	Supply and fixing of following sizes pvc conduit along with the accessories in surface / recess including painting in case of surface conduit, or cutting the walls and making good the same in case of recessed conduit as required.				
(a)	20 mm	Rmt.	52.00		
(b)	25 mm	Rmt.	70.00		
(c)	32 mm	Rmt.	30.00		
6	Supplying and fixing G.I metal box of new rolled sheet, min 18 gauge, corrosion resistant of following size (nominal size) on surface or in recessed with suitable size of Phenolic laminated sheet cover in the front including providing & fixing 3pin 5/6 AMP socket outlet and 5/6amp modular type switch connection, painting etc. as required.				
(a)	75mmx75mmx 60mm deep (for cables	Nos.	6.00		

	termination of ceiling fittings).				
(b)	100mmx100mm x60 mm deep	Nos.	4.00		
7	Supplying and making end termination with brass compression gland of following size PVC insulated PVC sheathed copper conductor armored cable.				
(a)	3.5x25 Sqmm	Each	1.00		
(b)	3.5x35 Sqmm	Each	1.00		
(c)	3.0 x 250 sqmm	Each	1.00		
8	Supplying, fixing, installation testing & commissioning of the following light fittings including lamp, ballast & accessories on the existing false ceiling ht. Up to 4.0 mt. Height or on the wall complete as required.				
(a)	600 x600 (39 W Led Light) (Philips Make (Philips green Square) Cat no. RC 140B	Each	8.00		
(b)	300 x300 (15W Led Light) (Philips Make (Philips green Square) Cat no. BBS 175	Each	1.00		
9	Earthing with G.I earth Pipe 3.0 m long x 40mm dia including accessories and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. complete as required / i.c extra for using salt & charcoal for pipe earth electrode as required.	Set	2.00		
10	Supplying & drawing 2.24 mm dia copper conductor wire for loop earthing in existing surface/ recessed conduit along with other wires etc. as required.	Rmt.	8.00		
11	Providing and fixing 6 SWG dia G,I, wire on surface or in recessed for loop earthing along with the existing surface/ Recessed cable as required.	Rmt.	6.00		
12	Providing & fixing 4.00 mm dia copper conductor wire for loop earthing in the existing surface or in recess conduit /submain wiring/cable etc. as required.	Rmt.	16.00		
	<u>OUT-DOOR LIGHTS & FRP POLES</u>				
13	Supply, Install, Test & Commission (S.I.T.C) of 4 M high FRP poles-tapered, round/square shaped with single bracket of 1.0 M at a tilt of 10 degree from horizontal and junction box.	Each	2.00		
14	Supply, Install, Test & Commission (S.I.T.C) of the following outdoors light complete with the complete gear associated with it to make it functional as required:				
(a)	LED based street light fixture with a power consumption of 18 Watts, type LSL 416 MP of Crompton greaves make.	Each	2.00		

15	Supply & Fixing of 1 no. PVC insulated PVC sheathed copper conductor armored cable of 1.1KV grade complete as required.				
(a)	3.5x25 Sq.mm Copper conductor on surface/trench	Rmt.	10.00		
	SDB				
16	Supplying & fixing of following sheet steel, MCB distribution board 240/415 volts on surface/recess complete with tinned copper busbar, neutral busbar, earth bar, din bar, detachable gland plate interconnection i/c painting earthing etc as required.				
(a)	2+8 Way DB (Incoming + Out going)	No	1.00		
(b)	4 + 12 Way DB (Incoming + Out going)	No	1.00		
17	Supply & Fixing of following MCB/ Isolator of the following poles in the existing MCB DB complete with connections, testing and commissioning, etc. as required. (Cat B)				
(a)	6 A , SP, MCB	No	9.00		
(b)	40 A, TPN , MCB	No.	1.00		
(c)	10A SP MCB	No.	6.00		
(d)	32A DP MCB	No.	1.00		
(e)	25A DP MCB	No.	1.00		
	TOTAL Rs				
	Note :				
	1.Unless otherwise specified the work is to be carried out as per CPWD specifications.				
	2. All the cables /wires shall confirm to the relevant IS Codes.				

SECTION -A (BOQ for Modifications / Additions / Alterations in existing CTI building located at BAREILLY (UP) on behalf of Private Broadcasters for FM Phase - III (Batch – 1)-----New work (Sanitary & Water Supply)

S.No.	Description	Unit	Qty	Rate	Amount
	<u>SANITARY WORK</u>				
1	Providing and fixing PVC waist pipe for sink and wash basin including PVC waste fitting complete 40mm dia	each	1.00		
2	Providing and fixing on wall face unplasticized Rigid PVC rain water pipes conforming to IS: 13592 Type A, including jointing with seal ring, clamps etc. conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socket pipes.				
a	110 mm dia pipe	rmt.	8.00		
3	Providing and fixing on wall face unplasticized PVC Moulded fitting/ accessories for unplasticised-PVC Rain water pipes conforming to IS: 4985 including Jointing with seal ring conforming to IS:5382 leaving 10 mm gap for thermal expansion				
a	Bend 87.5 Degree	nos.	2.00		
5	Providing and fixing CP brass pillar cock of approved quality and colour, 15 mm nominal bore, 107 mm long, weighing not less than 110 gms.	each	1.00		
6	Providing fixing stainless steel jali (grating) with or without hole for waste pipe for floor/Nahani Trap	each	2.00		
7	Providing and fixing toilet paper holder				
a	C.P brass	each	1.00		
8	Providing and fixing C.P. brass bib cock of approved quality to BECIL representative approval.				
(a)	15 mm nominal bore	each	1.00		
	TOTAL Rs				

SECTION -B (BOQ for Modifications / Additions / Alterations in existing CTI building located at BAREILLY (UP) on behalf of Private Broadcasters for FM Phase - III (Batch – 1)).....Repair works

S.No	Description	Unit	Qty	Rate	Amount
1	<u>REPAIRS TO BUILDING</u>				
1.1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 metres lead:				
(a)	With cement mortar 1:4 (1 cement : 4 fine sand)	sq.mt	4.00		
1.2	Making the opening in brick masonry including dismantling in floor or walls by cutting masonry and making good the damages to walls, flooring and jambs complete, to match existing surface to BECIL representative approval.				
(a)	For door/ window	sq.mt	2.00		
2	<u>FINISHING</u>				
2.1	Removing white or colour paint by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	sq.mt	440.00		
2.2	Wall/ Ceiling painting with plastic emulsion paint of approved brand and manufacture to give an even shade:				
(a)	One or more coats on old work	sq.mt	600.00		
2.3	Finishing walls with Acrylic Smooth exterior paint of required shade:				
(a)	Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface	sq.mt	48.00		
2.4	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade:				
(a)	One or more coats on old work	sq.mt	7.00		
3	<u>CEMENT PLASTER</u>				
3.1	15 mm internal cement plaster of mix: 1:6 (1 cement: 6 fine sand).	sq.mt	5.00		
3.2	18 mm cement plaster in two coats under layer 12 mm thick cement plaster 1:5 (1 cement : 5 coarse sand) finished with a top layer 6 mm thick cement plaster 1:6 (1 cement : 6 fine sand).	sq.mt	6.00		
4	<u>VITRIFIED FLOOR TILE</u>				

4.1	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS : 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), including grouting the joints with white cement and matching pigments etc., complete. (Basic rate of tile Rs 600/ sqm)	sq.mt	8.00		
5	DOORS AND WINDOWS				
5.1	Providing and fixing 12 mm thick pre laminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in paneling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of BECIL representative.				
(a)	Pre-laminated particle board with decorative lamination on both sides	sq.mt	1.00		
5.2	Providing and fixing glazing in aluminum door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket and snap bead etc. complete as per the architectural drawings and the directions of BECIL representative.				
(a)	With float glass panes of 5.50 mm thickness	sq.mt	1.00		
5.3	Providing and fixing double action hydraulic floor spring of approved brand and manufacture conforming to IS : 6315, having brand logo embossed on the body / plate with double spring mechanism and door weight up to 125 kg, for doors, including cost of cutting floors, embedding in floors as required and making good the same matching to the existing floor finishing and cover plates with brass pivot and single piece M.S. sheet outer box with slide plate etc. complete as per the direction of BECIL representative.				
(a)	With stainless steel cover plate minimum 1.25 mm thickness	each	1.00		
5.4	Filling the gap in between aluminum frame & adjacent RCC/ Brick/ Stone work by providing weather silicon sealant over backer rod of approved quality as per architectural drawings and direction of BECIL representative complete.				
(a)	Up to 5mm depth and 5 mm width	Rmt.	5.00		

5.5	Providing and fixing ISI marked anodized handles (anodic coating not less than grade AC 10 per IS:1868) transparent or Dyed to require colour or shade with necessary screw etc. complete. 250 X 63 X 4 mm as per direction of BECIL representative.	each	2.00		
5.6	Providing and fixing bright finished brass 100 mm mortice lock with 6 levers with necessary screw etc. complete (best make of approved quality).	each	3.00		
6	<u>GUTTER</u>				
	Dismantling, providing and fixing pre-coated galvanised steel sheet roofing accessories 0.50 mm (+ 0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 20 microns using self drilling/ self tapping screws complete: Gutter (600mm overall girth)	Rmt.	3.00		
7	<u>SANITARY WORK</u>				
7.1	Providing and fixing on wall face unplasticized Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with sealing ,clamps etc. conforming to IS : 5382, leaving 10 mm gap for thermal expansion,(i) Single socket pipes.				
a	110 mm dia pipe	Rmt.	3.00		
7.2	Providing and fixing on wall face unplasticized PVC Moulded fitting/ accessories for un plasticized-PVC Rain water pipes conforming to IS: 4985 including Jointing with seal ring conforming to IS:5382 leaving 10 mm gap for thermal expansion				
b	Bend 87.5 Degree	Nos.	4.00		
7.3	<u>BOTTLE TRAP</u>				
a	Providing and fixing CP brass Bottle Trap for Wash basin/sink.				
	Bottle trap 38 mm single piece moulded with height of 270 mm, effective length of tail pipe 260 mm from the centre of the waste coupling, 77 mm breadth with 25 mm minimum water seal, weighing not less than 263 gms.	each	1.00		
8	<u>ELECTRICAL WORK</u>				
8.1	S/F 15/16 Amp plate type switch along with 3 pin 15/16 Amp socket outlet on plate complete i/c modular box as required (Anchor Roma make and Havells)	Nos.	2.00		

8.2	Supplying, installation, testing & commissioning of light fittings on existing false ceiling.				
(a)	Supply & fixing 4X14 W CFL recessed down lighter with lamp complete as required Make - Phillips	Each	1.00		
8.3	Supply & Fixing of following type fluorescent fittings stove enameled control gear and side panels duly wired with heavy duty copper chokes, rotor, holder, starter, starter holder fluorescent tube & condenser for power factor improvement etc. complete as required.				
(a)	1x40 watt (As per Philips cat.no.TMC 55/136 HPF)	Each	2.00		
8.4	Supply & Fixing of decorative type wall mounted fittings complete with ballast, starter, starter holder and one no.20watt FL. Tube as required. (Philips cat no. TMS 200/120)	Each	1.00		
8.5	S.I.T.C of 150w HPSV flood light fitting complete with all accessories (as per Philips Cat.no SWF 230SK/150 W (SYM) along with 1 No. lamp and control gear box with the required necessary work including making earthing connection etc.as required.	Each	1.00		
9	SEPTIC TANK				
9.1	Cleaning of existing septic tank including removal of waste material from site all complete.	Each	1.00		
10	Dismantling, providing and fixing colour coated 0.5 mm Galvanised sheet of approved profile over the door & windows in the required width & protruding out 500 mm from wall panel. The canopy will be moulded at top & both vertical sides and will have all joints sealed with silicon with slope to drawings, complete with all fixtures, flashing, SS screws etc. Structural support system for such will be paid separately.				
(a)	New canopy	Sq.mt.	1.00		
(b)	Repairing/modification of existing canopy	Sq.mt.	3.50		
	TOTAL RS				